

Headline®

Fungicide

In-Furrow Application in Corn: Laying the Foundation for Success

Benefits of Headline® Fungicide Applied In-Furrow

- Aids in controlling soilborne *Rhizoctonia solani*
- Enhances root growth and seedling vigor
- Improves cold tolerance

Headline Fungicide Rate (fl oz/A)					
Rate per 1000 row feet (fl oz)	15" rows	20" rows	22" rows	30" rows	36" rows
0.1	3.5	—	—	—	—
0.2	7.0	5.2	4.7	3.5	3.0
0.3	10.5	7.8	7.1	5.2	4.5
0.4	—	10.4	9.5	6.9	6.0

In 30" rows, do not exceed 0.6 fl oz/1000 row feet.

Best Use Recommendations


- Use Rate: 0.1 to 0.4 fl oz/1000 ft row; see label for rate/A based on row spacing
- Maximum Rate/Season: 12 fl oz/A
- Minimum Volume of Water: 2.5 gal/A

Target Diseases

- *Rhizoctonia solani*

General Information

- Use Headline EC fungicide formulation when mixing with liquid fertilizer



BASF On-Farm trial 2012. Planted 4/23/12. Photo taken: 5/23/12.



150 years

 **BASF**

We create chemistry

Technical Information Bulletin

Benefits of Redline® Applied In-Furrow in Corn

- Redline will increase early season root development and enhance plant growth to maximize yield potential
- Superior chelation technology to provide nutrients to plants
- Insignificant risk of seedling root burn and stand reduction at recommended rates

Redline Best Use Recommendations

Convenience

- Redline formulation is nutrient balanced and efficient
- Low Use Rate: 3 GPA
- 3 gallons of Redline provides an equivalent to 1.2 qt of high quality 9% EDTA chelated zinc and 1 lb Soygreen®



Tankmix Partner

- Add Headline EC fungicide for increased early season growth and plant health


Principal Functioning Agents

- Total Nitrogen (N)6.0%
- Phosphorus (P)12.0%
- Potassium (K)2.0%
- Zinc (Zn).....1.0%
- Iron (Fe).....0.3%
- Manganese (Mn) 0.05%
- Copper (Cu)0.05%

Faster Emergence, Better Plant Health



Fullerton, NE, on-farm trial 2012. Planted 4/23/12; Photo taken: 5/23/12.



REDLINE®



Headline®
Fungicide

Always read and follow label directions

Headline is a registered trademark of BASF Corporation.
Redline is a registered trademark of West Central Distribution, LLC. Soygreen is a registered trademark of Lab JAER and is distributed exclusively by West Central Distribution, LLC.
©2015 BASF Corporation. All Rights Reserved. APN# 1410001 Headline-Redline-In-Furrow Corn
For more information on BASF Crop Protection products, visit agproducts.basf.us

BASF
We create chemistry